



**MODEL WEL-T-15 MOBILE TRANSPORT UNIT  
EASY LOAD SAFETY TRAILER FOR MANUAL TRANSPLANTERS  
AS FURTHER DESCRIBED BELOW: SPECIFICALLY DESIGNED TO SAFELY  
TRANSPORT, LOAD & UNLOAD PLANTER  
(SHOWN WITH OPTIONAL SPARE TIRE AVAILABLE AT ADDITIONAL COST)**

**THE WHITFIELD MODEL WEL-T-15 EASY-LOAD SAFETY MOBILE TRANSPORT UNIT IS DESIGNED TO TRANSPORT A TREE SEEDLING TRANSPLANTER AND TO ATTACH DIRECTLY TO TRUCKS FOR HIGHWAY USE.**

**THIS UNIT IS AN EXTRA HEAVY DUTY HAULER WITH 5200 POUND SPLIT-TORSION AXLE – A MUST FOR SAFELY LOADING, HAULING AND UNLOADING THE TREE SEEDLING TRANSPLANTER.**

**COMFORTABLY FITS CONTOURS OF TREE PLANTER AND IS BUILT LOW ENOUGH TO UTILIZE TRACTOR’S THREE-POINT HITCH LIFT. THE TREE TRANSPLANTER IS NOT A TYPICAL PIECE OF EQUIPMENT THAT SITS FLAT AND CAN BE EASILY TIED DOWN TO A FLAT SURFACE. EVEN WHEN OPERATOR OR TECHNICIAN ASSISTING DOES REMEMBER TO USE LEG STANDS SUPPLIED WITH ALL OUR TREE PLANTERS, IT IS HIGHLY PROBABLE THAT THE TREE PLANTER WOULD TILT AND BOUNCE AROUND ON THE COULTER (CUTTING) BLADE RESULTING IN SEVERE DAMAGE TO THAT PART.**

**IT IS OUR OPINION THAT NINETY-NINE (99) PERCENT OF THE UTILITY TRAILERS ON THE MARKET TODAY ARE TOO TALL TO ALLOW USE OF TRACTOR THREE POINT HITCH TO LOAD & UNLOAD A TREE SEEDLING TRANSPLANTER. THIS WOULD THEN REQUIRE AN EXTRA PIECE OF EQUIPMENT – SUCH AS A FORKLIFT OR TRACTOR POWERED LIFT APPARATUS**

**TRACTOR REMOVES TRANSPLANTER FROM THE WEL-T-15 MOBILE TRANSPORT UNIT. TRANSPLANTER IS ATTACHED TO TRACTOR WHILE IT IS STILL ON HAULER**

**THEN TRANSPLANTER IS REMOVED – USING TRACTOR THREE-POINT HITCH.**

**PLANTER WILL THEN BE REPLACED ON UNIT BY REVERSE PROCESS OF PREVIOUS TWO STEPS.**



**INFORMATION FOR FLATBED TRUCK SHIPPING:**

**UNIT 14’ LONG X 7’3” WIDE X 8’ HIGH**

**WEIGHT: APPROXIMATELY 1000 LB.**

**PRICE: \$ 2,695.00 F.O.B. MABLETON, GEORGIA ♦ USA**